

**KERALA IRRIGATION INFRASTRUCTURE DEVELOPMENT
CORPORATION LTD.**

KI IDC/682/2020/PLE1

14/03/2025

QUOTATION NOTICE

Sealed quotations are invited for the "KI IDC Head Quarters shifting to KWA building- Partition works for the Office Space

QUOTATION NO: 04/2025-26

SINO	QUOTATION NO	DETAILS OF WORK
1	QUOTATION NO: 04/2025-26	Furnishing the toilet blocks by providing tiles and all bathroom fittings after dismantling the existing, providing and fixing water supply and sewerage system and providing and laying vitrified floor tiles in the office building wherever required.

1. Bidders can drop their quotations within 4 days, after the issue of this Quotation Notice in the office of the undersigned at Kerala Irrigation Infrastructure Development Corporation Ltd. (KI IDC) T.C. 84/3 (Old 36/1), NH66 Bypass Service Road, Near Eanchakkal Junction, Chackai P.O., Thiruvananthapuram – 695 024.
2. The quotations will be opened on 17-03-2025 at 3.00 PM hours. Quotations will be opened in presence of bidders who may like to attend.
3. The words " KI IDC Head Quarters shifting to KWA building- Partition works for the Office Space" should be inscribed on envelope of the quotation.
4. **The bidder must quote the total amount (including all taxes) for the items as per the attached schedule.**
5. All the quotations must be submitted with photocopy of PAN card, GST Registration Certificate
6. Bidder shall be responsible for the payment of all type of taxes, as applicable.
7. **The bidder shall visit the site before participating in bid process for the works and shall be deemed to be familiar with the site conditions.** The site are available for viewing for bidders on any working days within office hours at the respective site. For assistance, please contact: +91 9544932079 (Project Coordinator)
8. Any damage to the existing building/structure/fencing/wiring/sewer lines/water lines/telephone cables/power cables etc. during carriage of material or otherwise shall be rectified/made good by the applicant/firm.
9. The successful bidder shall be responsible for and shall comply all safety measures, labour regulations, traffic rules & timings, provisions etc.
10. The bidder shall be liable for any mis-happening, damage at site or outside. KI IDC shall not be responsible for that.
11. In case KI IDC is not satisfied with the performance of bidder or progress of works, KI IDC has the right to cancel the work order. The bidder shall not be entitled for any compensation from KI IDC.

12. KIIDC reserves the right to postpone or cancel the tender without showing any reason.
13. In those cases where the selected bidder does not produce any required documents or submit the performance security or does not enter into agreement within the specified time limit, the bidder shall be debarred in future from participating in all Government bids for three years and will be recommended for blacklisting by the competent authority.



Chief Executive officer

കേരളസർക്കാർ

കേരള ഇറിഗേഷൻ ഇൻഫ്രാസ്ട്രക്ചർ ഡെവലപ്മെന്റ് കോർപ്പറേഷൻ

KI IDC/682/2020/PLE1

12/03/2025

Quotation No: QUOTATION 04/2025-26

കൊട്ടേഷൻ പരസ്യം:


മാനേജിംഗ് ഡയറക്ടർ, കേരള ഇറിഗേഷൻ ഇൻഫ്രാസ്ട്രക്ചർ ഡെവലപ്മെന്റ് കോർപ്പറേഷൻ (കെ.ഐ. ഐ. ഡി. സി) വേണ്ടിതാഴെ പറയുന്ന പ്രവൃത്തിക്ക്

1. Furnishing the toilet blocks by providing tiles and all bathroom fittings after dismantling the existing, providing and fixing water supply and sewerage system and providing and laying vitrified floor tiles in the office building wherever required.

അംഗീകൃത സ്ഥാപനങ്ങൾ/വ്യക്തികളിൽ നിന്നും മുദ്രവെച്ചുകവറുകളിൽ കൊട്ടേഷൻ ക്ഷണിച്ചുകൊള്ളുന്നു. കൊട്ടേഷൻ പ്രമാണങ്ങളും മറ്റു വിശദവിവരങ്ങളും 17-03-2025 പകൽ 3.00 PM മണിക്ക് മുൻപ് താഴെ ഒപ്പുവെച്ചിട്ടുള്ള ഉദ്യോഗസ്ഥന്റെ കാര്യാലയത്തിൽ സ്പീഡ്പോസ്റ്റ്/പോസ്റ്റ് മുഖാന്തിരം എത്തിക്കേണ്ടതാണ്. പ്രവൃത്തിയുടെ ഇനം തിരിച്ചുള്ളതുകയാണ് രേഖപ്പെടുത്തേണ്ടത്. കൊട്ടേഷനിൽ രേഖപ്പെടുത്തുന്ന തുക നികുതിയോടുകൂടിയുള്ളതായിരിക്കണം. നിർദ്ദിഷ്ട സമയം കഴിഞ്ഞ് സമർപ്പിക്കുന്ന കൊട്ടേഷനുകൾ സ്വീകരിക്കുന്നതായിരിക്കില്ല. കേരള സർക്കാരിൻറെയും പൊതുമരാമത്തവകുപ്പിലേയും കൊട്ടേഷനെ സംബന്ധിക്കുന്ന മറ്റെല്ലാ വ്യവസ്ഥകളും ഈ കൊട്ടേഷന് ബാധകമാണ്.

കൊട്ടേഷൻ അടങ്ങുന്ന കവറിന്റെ മേലെഴുത്തിൽ പ്രവൃത്തിയുടെ പേര് സൂചിപ്പിക്കേണ്ടതാണ്. പ്രസ്തുത കൊട്ടേഷനുകൾ അതേ പ്രവൃത്തിദിവസം വൈകുന്നേരം 3.00 PM-ന് നടപടിക്രമങ്ങൾപാലിച്ച് മാനേജിംഗ് ഡയറക്ടറോ അദ്ദേഹം ചുമതലപ്പെടുത്തുന്ന ഉദ്യോഗസ്ഥനോ തുറക്കുന്നതാണ്. കേരള സർക്കാരിൻറെ കൊട്ടേഷനെ സംബന്ധിച്ച നിബന്ധനകളും ഈ കൊട്ടേഷനു ബാധകമാണ്.

മാനേജിങ് ഡയറക്ടർക്കു വേണ്ടി,

 s/d
ചീഫ് എക്സിക്യൂട്ടീവ് ഓഫീസർ

Quotation No. 04/2026

Quotation Schedule

Sl.No	Item Specification	Quantity	Rate	Amount
1	Providing and laying vitrified floor tiles of size 600x600 mm confirming to IS 15622 of approved makes including all colours and shades laid using cement mortar/ joint material including cost of all materials slurry etc complete (Tiles will be selected by KIIDC)	180 M ²		
2	Providing and fixing first quality ceramic glazed wall tiles confirming to IS 15622 of approved make in all colours and shades of any size as approved by engineer in charge including jointing with slurry/ paste, pointing etc complete including cost of all materials labour, transportation etc complete	120 M ²		
3	Providing and fixing white vitreous china pedestal type water closet(European type W.C.pan)with seat and lid , 10 liter low level white P.V.C flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fitting and fixture complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	7 nos		
4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630 X 450 mm with a pair of 15 mm C.P. brass pillar taps	9 nos		
5	Providing and fixing brass bib cock of approved quality :20 mm nominal bore	9 nos		
6	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fitting of approved quality and colour, weighting not less than 105 gms	4 nos		

7	Proving and fixing(576 CHR) HEALTH FAUCET OF SUPERIOR QUALITY JAGUAR OR EQUIVALENT BRAND	9 nos		
8	Dismantling the old plaster, existing door and windows (Steel , wood or Plastic) dismantling the tile works in floors and walls and cleaning the surface including disposal of rubbish to the dumping ground with in 50 meters lead.	30 M ²		
9	Ciment plastering 12 mm thick of mix 1:6 wherever necessary as per directions of the department officials	60 M ²		
10	Proving and fixing all necessary PVC pipes and fittings of different sizes as required at site including jointing of pipes testing of joint etc complete as required for the office building so as to ensure good quality water supply and drainage system after checking the existing plumbing system, making good the same including cost of all materials pipes, earthwork excavation wherever required as per directions of the department officials.(The quotationer should visit the site , test the existing system and quote the item accordingly)	1 Set		
11	Supplying and Providing all required sealing materials grid type for the existing bathrooms which are being renovated.	30 M ²		
12	Removing and replacing the existing broken glass of ventilators and windows including cost of glass including labour charge , transportation etc complete as per directions of the department officials	12 nos		
	Total			
	Amount in words			

ce

12/3
CEB