

**KERALA IRRIGATION INFRASTRUCTURE DEVELOPMENT
CORPORATION LTD.**

KI IDC/59/2026-OA3

02/03/2026

QUOTATION NOTICE

Sealed quotations are invited for the work “Construction of compound wall and gate for Hilly Aqua Plant at Kattappana- Idukki”

QUOTATION NO: 30/2025-2026

<u>QUOTATION NOTICE</u>			
Name of Work: “Construction of compound wall and gate for Hilly Aqua Plant at Kattappana- Idukki			
SINO	QUOTATION NO	DETAILS OF MATERIALS	QUANTITY
1	QUOTATION NO: 30/2025-2026	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	6.338 cum
2		4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	1.118 cum
3		7.1.1 Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone	4.455 cum

		coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with:Cement mortar 1:6 (1 cement : 6 coarse sand)	
4		5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.570 cum
5		5.9.1 Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete	4.800sqm
6		5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	34.200 kilogram
7		50.6.2.2 Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	2.126 cum
8		50.6.3.2 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x10 cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level for 10 cm thick wall in : CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding complete	1.148cum

9		13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	10.463 sqm
10		13.47.1 Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	36.783 sqm
11		10.25.2 Item Shifted to Sub head 14 as item 14.73 Item Shifted to head 14 as item 14.74 Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	970.018 kg
12		13.52.1 Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	22.850 sqm
13		OD52143/2025-2026 Supply and fixing signage in English. The signage letters will be made with premium Quality vinyl sheet of approved colour, pasted on 3mm thick aluminum composite panel backing. The signage will be either fixed on the	6000.00 sqcm

		wall with the screws & double tape or hanged from the false ceiling with the help of hooks & chains where ever required	
--	--	---	--

1. The bidder who has quoted the lowest amount shall be considered subject to the prevailing government norms
2. Bidders can drop their quotations within 7 days, after the issue of this Quotation Notice in the office of the undersigned at Kerala Irrigation Infrastructure Development Corporation Ltd. (KIIDC) Jalabhavan Campus, Vellayambalam P.O., Thiruvananthapuram – 695 033
3. The quotations will be opened on 10.03.2026 at 16:30 hours. Quotations will be opened in presence of bidders who may like to attend.
4. The words “Construction of compound wall and gate for Hilly Aqua Plant at Kattappana- Idukki” should be inscribed on envelope of the quotation.
- 5. The bidder must quote the total amount (including all taxes) for the items as per the attached schedule.**
6. An EMD of Rs. 8,750/- in the form of Demand Draft, drawn in favour of the Managing Director, KIIDC Thiruvananthapuram should be included along with the quotation.
7. All the quotations must be submitted with photocopy of PAN card, GST Registration Certificate
8. Bidder shall be responsible for the payment of all type of taxes, as applicable.
- 9. The bidder shall visit the site before participating in bid process for the works and shall be deemed to be familiar with the site conditions.**
10. The bidder shall arrange to remove the material from the site at his own cost.
11. Any damage to the existing building/structure/fencing/wiring/sewer lines/ water lines/telephone cables/power cables etc. during carriage of material or otherwise shall be rectified/made good by the applicant/firm.
12. During the process of Transportation, the Material should be covered by a thick covering sheet. Observe the prevailing traffic rule and regulations.
13. The successful bidder shall be responsible for and shall comply all safety measures, labour regulations, traffic rules & timings, provisions etc.

14. The bidder shall be liable for any mis-happening, damage at site or outside. KIIDC shall not be responsible for that.
15. In case KIIDC is not satisfied with the performance of bidder or progress of works, KIIDC has the right to cancel the work order and forfeit the EMD. The bidder shall not be entitled for any compensation from KIIDC.
16. KIIDC reserves the right to postpone or cancel the tender without showing any reason.
17. In those cases where the selected bidder does not produce any required documents or submit the performance security or does not enter into agreement within the specified time limit, the bidder shall be debarred in future from participating in all Government bids for three years and will be recommended for blacklisting by the competent authority.


Chief Executive officer

KERALA IRRIGATION INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

QUOTATION 30/2025-26

Name of work: Construction of compound wall and gate for Hilly Aqua Plant at Kattappana- Idukki

SI NO	ITEM DESCRIPTION	QUANTITY	UNITS	RATE IN FIGURES TO BE ENTERED BY THE BIDDER (incl GST)		AMOUNT IN FIGURES TO BE ENTERED BY THE BIDDER (incl GST)	
				In Figures	In Words	In Figures	In Words
1	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	6.338	cum				
2	4.1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 Cement :	1.118	cum				

	3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)						
3	7.1.1 Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with:Cement mortar 1:6 (1 cement : 6 coarse sand)	4.455	Cum				
4	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size derived from natural sources)	0.570	Cum				

5	5.9.1 Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	4.800	sqm				
6	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	34.200	Kilogram				
7	50.6.2.2 Solid masonry using pre cast solid blocks (factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	2.126	cum				
8	50.6.3.2 Solid block masonry using pre cast solid	1.148	cum				

	blocks (Factory made) of size 40x20x10 cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level for 10 cm thick wall in : CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding complete						
9	13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	10.463	sqm				
10	13.47.1 Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	36.783	sqm				
11	10.25.2 Item Shifted to Sub head 14 as item 14.73 Item Shifted to head 14 as item 14.74	970.018	kg				

	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works						
12	13.52.1 Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	22.850	sqm				
13	OD52143/2025-2026 Supply and fixing signage in English. The signage letters will be made with premium Quality vinyl sheet of approved colour, pasted on 3mm thick aluminum composite panel backing. The signage will be either fixed on the wall with the screws & double tape or hanged from	6000.00	sqcm				

	the false ceiling with the help of hooks & chains where ever required						
--	---	--	--	--	--	--	--

TOTAL: Rs _____

I do hereby submit willingness to execute the above work for a total amount of Rs. _____ (Including GST)
 (Words: _____)
 (Including GST)

SIGNATURE OF THE BIDDER

Name of Bidder:
 Address:
 GST No:
 Contact No:


 CHIEF EXECUTIVE OFFICER